

New methods for large dynamical range problems in planetary formation

D. S. McNeil^{1*} and R. P. Nelson¹

¹*Astronomy Unit, School of Mathematical Sciences, Queen Mary, University of London, Mile End Road, London, UK E1 4NS*

Accepted 2008 October 19. Received 2008 April 1.

ABSTRACT

Modern N-body techniques for planetary dynamics are generally based on symplectic algorithms specially adapted to the Kepler problem. These methods have proven very useful in studying planet formation, but typically require the timestep for all objects to be set to a small fraction of the orbital period of the innermost body. This computational expense can be prohibitive for even moderate particle number for many physically interesting scenarios, such as recent models of the formation of hot exoplanets, in which the semimajor axis of possible progenitors can vary by orders of magnitude. We present new methods which retain most of the benefits of the standard symplectic integrators but allow for radial zones with distinct timesteps. These approaches should make simulations of planetary accretion with large dynamical range tractable. As proof-of-concept we present preliminary science results from an implementation of the algorithm as applied to an oligarchic migration scenario for forming hot Neptunes.

Key words: methods: numerical – celestial mechanics – Solar system: general

1 INTRODUCTION

Dynamical timescales in the solar system vary widely. For example, Mercury’s orbital period is 0.24 yr, Pluto’s is 250 yr, and comets in the Oort cloud can have periods of ~ 10 Myr, for a difference of over seven orders of magnitude. The disparity in timescale increases if we also consider not merely orbital period but period at periape, such as in Sun-grazing comets which can come within a few solar radii, or the orbits of moons and satellites. The age of our solar system is ~ 4.6 Gyr, and relevant formation timescales are believed to be on the order of a few million years (for the accretion of giant planet cores) to tens of millions of years (for the formation of the Earth) to hundreds of millions of years (for possible late-stage rearrangement of the outer solar system, e.g. Tsiganis et al. 2005).

The enormous number of orbits required presents a considerable challenge for numerical studies of planet formation. In N-body studies of galaxy formation, by contrast, the number of dynamical times is low, and therefore the emphasis has been on increasingly complex modelling of the physics and ever-larger numbers of particles, both of which are amenable to parallelization. Although multiprocessor codes can offer major benefits even for planetary simulations, the large number of timesteps limits the particle

number to a regime where latency issues loom large. The planetary problem is simply, and inescapably, hard.

The difficulties are yet greater for studies of the formation of hot Neptunes, giant planets orbiting very close to the parent stars. These planets are unlikely to have formed in situ, suggesting that gas disc induced migration will play an important role. For example, GJ436b is a hot transiting Neptune (Butler et al. 2004) whose density is $\sim 1.69 \text{ g/cm}^3$ (Torres 2007). This suggests it is a true Neptune analogue (i.e. an ice giant, not a small gas giant or a large, rocky super-Earth), which raises the question of where its ice originated. In the standard models of the minimum-mass solar nebula, the snow line beyond which ices can condense is ~ 2.7 AU. Therefore one obvious toy scenario for the history of GJ436b is that the planet started its life in the outer regions of the disc, and then migrated in due to interactions with the gas, possibly growing en route.

At present, the most elegantly constructed general integrator for doing late-stage N-body studies of planet formation is SyMBA (Duncan et al. 1998), a Kepler-adapted symplectic integrator capable of resolving close encounters, which is descended from the original methods of Wisdom & Holman (1991) and Kinoshita et al. (1991). There are several implementations of the algorithm and its variants available, including a parallel version which has been useful in studying terrestrial accretion (McNeil et al. 2005), and so it would be natural to apply these codes imme-

* E-mail: d.mcneil@qmul.ac.uk

diately. Unfortunately, a direct treatment of the hot Neptune problem is completely beyond the reach of standard methods, at least at the usual resolution. The orbital period at 0.05 AU is ~ 0.01 yr, 30 times smaller than at 0.5 AU (a respectable inner boundary for studies of the formation of the Earth). Since migration over several AU plays a role, we cannot concentrate on a narrow region (e.g. Kokubo & Ida 1998) but must build a more global model, requiring large numbers of particles. Furthermore, since the formation and migration timescales will be important and often comparable, some common tricks for speeding up simulations (such as increasing the collisional radius) may be dangerous.

These formation scenarios are of considerable interest, and are not easily studied using current numerical and computational technology; they are messy systems, with many non-Hamiltonian forces and events, and not clean celestial mechanics problems; and there seems to be a promising direction for improvement. We therefore seek to develop new integrators which will allow us to address these problems. Given the difficulties, we are willing to consider approximations which we would hesitate to use in other situations, such as a detailed study of long-term chaos in the outer solar system. We will instead sacrifice some precision while preserving reliability in the hopes of exploring otherwise inaccessible science: in this situation practicality beats purity.

Fortunately, the very feature which makes the problem so challenging – the wide dynamical range – opens up possibilities for new methods. SyMBA and its cousins use a common timestep for all (non-encountering) objects which is set by the minimum pericentric distance. This limitation can be worked around when objects only occasionally enter the innermost regions (Levison & Duncan 2000) but it reduces to using unacceptably slow Bulirsch-Stoer integration when there is always an object in the innermost regions, as we expect in our models. However, we note that for an inner edge of 0.05 AU, a timestep of ~ 0.0005 yr would be necessary, but if the inner edge of the problem were 1 AU, a timestep of 0.05 yr would suffice. This suggests that using the common small timestep results in objects beyond 1 AU being ‘over-integrated’ by roughly a factor of 100. If we could somehow use the larger timestep for the outer objects, then since most particles in simulations of oligarchy tend to be in the outer regions (where formation times are longer), we might be able to recover something like the standard run times. Indeed, a decade and a half ago, Saha & Tremaine (1994) were already building mixed-variable integrators with different timesteps associated with each planet, so there is precedent.

Therefore we set out to construct a new multizone method using recent numerical technology which allowed for small timesteps in the inner regions and large timesteps in the outer regions. We had several desired properties:

(1) Symplecticity, or at least near-symplecticity, is highly desirable. By contrast, time-reversibility (in the absence of mergers and dissipational forces) is necessary, as many of the good conservation properties of symplectic integrators are inherited from their reversibility.

(2) SyMBA’s underlying integrator step is very robust, especially at low eccentricities, and has extensive field-testing (both in Duncan and Levison’s SWIFT and in John Chambers’s MERCURY). An integrator which reduces to

this proven approach for objects which are in the same zone is preferable.

(3) Correct close encounter handling is vital. Although we may be willing to accept a decrease in encounter accuracy in a few locations (such as at the zone boundaries), the vast majority of encounters must be treated using a method known to be reliable. More generally, force inaccuracies should be limited to distant interactions, as in fast force techniques such as treecodes.

(4) Any discontinuities caused by the existence of distinct timestep zones should be kept to a minimum, and at or below second order if possible.

By using existing techniques in the literature, we develop integrators which meet the above criteria, choosing at every branch point the simplest scheme which seems likely to work. We combine the Hamiltonian splitting of Duncan et al. (1998) with a multistep approach inspired by Saha & Tremaine (1994), use the transitioning approach of Chambers (1999) to preserve symplectic behaviour, and derive new transition functions to make the scheme sufficiently smooth.

In §2 we briefly review the use of symplectic methods in planetary dynamics. In §2.1 we introduce the Kepler-adapted mixed-variable symplectic integrators; in §2.2 and §2.3 we explain methods for treating close encounters between planets and between a planet and the Sun, respectively; and in §2.4 we discuss integrators which allow individual timesteps. In §2.5 we construct the new integrators, and in §2.6 we develop appropriate transition functions. We present tests of the method in §3 and a discussion in §4. We conclude in §5.

2 SYMPLECTIC METHODS FOR KEPLERIAN POTENTIALS

Geometric integrators are numerical integration methods which attempt to build the properties of the equations and their solutions into the integrators themselves, properties such as symmetries and their corresponding conserved quantities (Yoshida 1993). This matching of geometry between the problem and the solver can lead to improvements in accuracy and robustness, as well as dramatic increases in speed. Symplectic integrators are geometric integrators where the geometry of interest is Hamiltonian, and the conserved quantity is the natural area element, the Poincaré 2-form $d\mathbf{p}_i \wedge d\mathbf{q}^i$, where $\mathbf{q}$ and $\mathbf{p}$ are the usual generalized positions and momenta, respectively, with summation over particles i with mass m_i .) A symplectic integrator can be constructed via operator methods or frequency maps; we restrict ourselves to operators.

For some Hamiltonian H , if we divide it (arbitrarily but conveniently) into a kinetic term H_T and a potential term H_V ,

$$H = H_T + H_V \quad (1)$$

we can approximate the evolution under H by a second-order time-reversible drift-kick-drift ‘leapfrog’ scheme

$$H^\tau \approx H_T^{\tau/2} H_V^\tau H_T^{\tau/2} \quad (2)$$

where H_X^τ is the operator generated by the Hamiltonian term H_X , and τ is the timestep. This integrator solves

a nearby ‘surrogate’ Hamiltonian $\tilde{H} = H + H_{\text{err}}$ where $O(H_{\text{err}}) = \tau^2$, using ‘solves’ in the sense of physics and not mathematics. (H_{err} is a purely formal series which need not converge in general, and certainly need not converge at the large timesteps used in practice, but is well-approximated by its first few terms.)

2.1 Wisdom-Holman method

The work of Wisdom & Holman (1991) and Kinoshita et al. (1991) sparked a dramatic revolution in planetary integrations by specializing the general techniques of symplectic integration to the unique properties of Keplerian dynamics in the solar system. It is well known that the orbits of a system of small bodies around a large central mass are very nearly conic sections, and this Keplerian motion can be advanced (almost) analytically. This suggests that instead of dividing the Hamiltonian into kinetic and potential terms as in the standard leapfrog, we should divide it into a Keplerian term and a term corresponding to the perturbations between the planets:

$$H = H_{\text{Kep}} + H_{\text{int}} \quad (3)$$

The difficulty arises in finding a canonical set of coordinates in which the N-body Hamiltonian takes this shape. Wisdom & Holman (1991) discovered that using Jacobi coordinates succeeds. In this coordinate system, the position and momentum of the j th object (of N planets, where the masses are given by the m_j , and the Sun is $j = 0$) are given relative to the centre of mass of the inner bodies, i.e. those with index $k < j$. They write

$$H_{\text{Kep}} = \sum_{j=1}^N \left(\frac{|\mathbf{p}'_j \cdot \mathbf{p}'_j|}{2m'_j} - \frac{Gm_j m_0}{|\mathbf{q}'_j|} \right) \quad (4)$$

and

$$H_{\text{int}} = \sum_{j=1}^N \left(\frac{Gm_j m_0}{|\mathbf{q}'_j|} - \frac{Gm_j m_0}{\mathbf{q}_{j0}} \right) - \sum_{j=1}^{N-1} \sum_{k=j+1}^N \frac{Gm_j m_k}{\mathbf{q}_{jk}} \quad (5)$$

where the primed quantities are Jacobi coordinates and $\mathbf{q}_{jk} = |\mathbf{q}_j - \mathbf{q}_k|$. In the absence of close encounters, $H_{\text{int}} \ll H_{\text{Kep}}$ and the non-Keplerian perturbations on the orbits due to mutual interactions are small. We can construct a second-order integrator as before, where the new H_{Kep} drifts are ‘rolls’ along the Keplerian conic section, and the H_{int} kicks are the Cartesian perturbations between the planets; hence the name ‘mixed-variable symplectic’ (MVS; Saha & Tremaine 1992) has been used for integrators of this type, as the integrations are in effect carried through in both Cartesian and Keplerian variables. This approximation to the orbit is vastly superior to the linear-path kinetic/potential decomposition, and the symplecticity provides robustness and stability. As a result, one can use much larger timesteps than would be otherwise permissible, making planetary simulations running for the age of the solar system feasible (e.g. Duncan et al. 1995).

For a brief review of the history of various mapping methods in solar system dynamics, see ch. 9 of Murray & Dermott (1999). Wisdom (2006) also provides a useful review.

2.2 Close encounters between planets

Despite its many benefits for studies of well-separated planets for long timescales, the use of Jacobi coordinates in the MVS approach limits its applicability. Studies of planetesimal accretion, a highly chaotic and stochastic process, require the ability to handle radial reordering of objects and to resolve close encounters. In the Wisdom-Holman mapping, the coordinate frame depends upon a fixed ordering of the objects, and cannot be updated as the system changes without breaking symplecticity. There is also no natural way to treat encounters: first, by varying the timestep you lose the symplecticity of the integration as the composition of two symplectic steps need not be symplectic; and second, even if one could vary the timestep, the coupling between objects in the Jacobi scheme means that all external objects are also implicitly involved, so an encounter cannot be treated independently. We would prefer an integrator in which each planet was treated equivalently and which could adapt the timestep when planets strongly interact.

After some early experiments (e.g. Levison & Duncan 1994), a superior solution to the problem was presented in Duncan et al. (1998) (hereafter DLL98) which used an ingenious choice of coordinates to avoid the coupling between planets, a particular choice of Hamiltonian splitting to ensure that all planets were treated equally, and a clever decomposition of the potential into shells to allow effective changes in the timestep. The authors developed a ‘democratic heliocentric’ (DH) method, where ‘democratic’ means ‘symmetric with respect to the labelling of the planets’, and which avoids the particle entanglement of Jacobi coordinates. In these coordinates, one uses heliocentric positions but barycentric momenta. (Note that the same system is called ‘mixed-centre’ by Chambers 1999 and ‘canonical heliocentric’ by Wisdom 2006.)¹ To be explicit, from $\mathbf{q}$ and $\mathbf{p}$ they compute new conjugate coordinates $\mathbf{Q}$ and $\mathbf{P}$, such that

$$\mathbf{Q}_i = \begin{cases} \frac{1}{m_{\text{tot}}} \sum_{j=0}^N m_j \mathbf{q}_j & i = 0 \\ \mathbf{q}_i - \mathbf{q}_0 & i \neq 0 \end{cases} \quad (6)$$

and

$$\mathbf{P}_i = \begin{cases} \sum_{j=0}^N \mathbf{p}_j & i = 0 \\ \mathbf{p}_i - \frac{m_i}{m_{\text{tot}}} \sum_{j=0}^N \mathbf{p}_j & i \neq 0 \end{cases} \quad (7)$$

This results in a new form for the Hamiltonian,

$$H(\mathbf{Q}_i, \mathbf{P}_i) = H_{\text{Sun}} + H_{\text{Kep}} + H_{\text{int}} \quad (8)$$

where

$$H_{\text{Sun}} = \frac{1}{2m_0} \left| \sum_{i=1}^n \mathbf{P}_i \right|^2, \quad (9)$$

$$H_{\text{Kep}} = \sum_{i=1}^n \left(\frac{|\mathbf{P}_i|^2}{2m_i} - \frac{Gm_i m_0}{|\mathbf{Q}_i|} \right), \quad (10)$$

$$H_{\text{int}} = - \sum_{i=1}^{n-1} \sum_{j=i+1}^n \frac{Gm_i m_j}{|\mathbf{Q}_i - \mathbf{Q}_j|}. \quad (11)$$

¹ The temptation to suggest yet another name is resisted only with difficulty.

H_{Sun} generates a linear drift of particles' positions (taking its name from the fact it is determined by the barycentric momentum of the Sun), H_{Kep} corresponds to a pure Kepler orbit, and H_{int} , as before, is the term due to the interaction of the particles. Note that – unlike with the Wisdom-Holman mapping (eqs. 4 and 5) – an encounter between two particles is separable, in that the terms involving the positions and momenta of the two objects can be pulled out of H_{Kep} and H_{int} . (In contrast, H_{Sun} is not separable in this way; we return to this subject.)

As Wisdom (2006) notes, the same canonical heliocentric coordinate system was used in previous work (Touma & Wisdom 1993, 1994), with different Hamiltonian splittings. For example, Touma & Wisdom (1993) used the alternate splitting

$$H'_{\text{Sun}} = \frac{1}{m_0} \sum_{1 \leq i < j}^n \mathbf{P}_i \mathbf{P}_j \quad (12)$$

$$H'_{\text{Kep}} = \sum_{i=1}^n \left(\frac{|\mathbf{P}_i|^2}{2\mu_i} - \frac{Gm_i m_0}{|\mathbf{Q}_i|} \right), \quad (13)$$

where μ is the reduced mass. This splitting has the advantage that it preserves Kepler's semimajor axis-period relationship. However, the use of the reduced mass means that two objects with the same position and velocity but different masses will experience different Kepler drifts and different linear drifts, which can present difficulties for treating close encounters (DLL98, §4). In this sense the DLL98 splitting is more 'democratic', at the cost of being slightly less accurate for a given orbit. Accordingly, we will use 'canonical heliocentric' for the coordinate system itself, and reserve 'democratic heliocentric' for the specific three-term Hamiltonian splitting used in DLL98 and described by eq. 8.

From this DH splitting, they construct a second-order integrator which will be the basic DH step. Following the conventional notation, let L be the operator generated by H_{Sun} (L for 'linear drift'), let K correspond to H_{int} (K for 'kick'), and let D correspond to H_{Kep} (D for 'drift'). Using this form, the system is advanced one timestep τ by applying

$$H^\tau \approx L^{\tau/2} K^{\tau/2} D^\tau K^{\tau/2} L^{\tau/2} \quad (14)$$

As naive adaptive timestepping changes the surrogate Hamiltonian and thus breaks symplecticity, DLL98 develop a technique involving recursive subdivision of the timesteps along with decomposing the force into a series of shells around the particles, and associating each force shell with a different timestep. Similar approaches had been attempted previously in molecular dynamics (Skeel & Biesiadecki 1994) with limited success, but DLL98 realized that there were relevant smoothness constraints on the transition from shell to shell.

Starting from the basic DH step, we relabel K, D as K_0, D_0 . We replace the D^τ by a sequence of M_i smaller substeps, $[K_i^{\tau/2M_i} D_i^{\tau/M_i} K_i^{\tau/2M_i}]^{M_i}$ where K_i is an interaction term to be defined, and then repeat the process indefinitely

at higher index:

$$\begin{aligned} H &\approx L^{\tau/2} K_0^{\tau/2} D_0^\tau K_0^{\tau/2} L^{\tau/2} \\ &\approx L^{\tau/2} K_0^{\tau/2} [K_1^{\tau/2M_1} D_1^{\tau/M_1} K_1^{\tau/2M_1}]^{M_1} K_0^{\tau/2} L^{\tau/2} \\ &\approx L^{\tau/2} K_0^{\tau/2} [K_1^{\tau/2M_1} \\ &\quad [K_2^{\tau/2M_1M_2} D_2^{\tau/M_1M_2} K_2^{\tau/2M_1M_2}]^{M_2} \\ &\quad K_1^{\tau/2M_1}]^{M_1} K_0^{\tau/2} L^{\tau/2} \\ &\approx \dots \end{aligned} \quad (15)$$

Each of the above integrators, as well as the $i \rightarrow \infty$ limit, has a fixed surrogate Hamiltonian; the timestep τ never changes. Since the D_i terms commute with themselves, then if succeeding K_i terms are merely the identity operators the neighbouring D_i terms reduce to one large drift. For example, if $K_i = 0$ for all $i > 0$, then the integrator reduces to the basic DH step with timestep τ . However, if K_2 were nonzero, then since D_i and K_i do not commute, the reduction would not occur and the integrator would act on the smaller timestep. In this scheme, an infinite number of terms are always active, but need not actually be considered unless the intervening K_i terms are nonzero. The problem becomes finding a decomposition of the potential H_{int} generating the K terms $K_0, K_1, K_2, \dots$ which will (1) recover the standard DH step when no close encounters are occurring and the larger timestep τ suffices, i.e. $K_0 = K$, and $K_i = 0$ for $i > 0$; (2) always sum to the correct amount of force, i.e. $\sum_i K_i = K$; and (3) do so in a sufficiently smooth fashion. To construct such a decomposition, DLL98 imagine a decreasing sequence of shell radii $R_1 > R_2 > \dots$ with a corresponding decomposition of the potential into $V_1, V_2, \dots$ where the magnitude of the potential terms V_k smoothly decreases to zero outside the shell range. By studying the error Hamiltonian they find several necessary conditions on the decomposition relating to the smoothness of the transition of the potential from term to term.

The resulting algorithm SyMBA, combining the DH coordinate system with the recursively subdivided smoothly-transitioning zone operators, works remarkably well. Nevertheless, it is challenging to implement and difficult to test. For example, a correct version of the algorithm will often show worse energy and angular momentum conservation on a given encounter than a subtly incorrect one, requiring large test suites; and since the solution is very finely tuned to the planetary problem, off-the-shelf routines are of little use.

Chambers (1999) developed a much simpler though more expensive approach. Of the three major advances in SyMBA – DH coordinates, the smoothness conditions on motion between operators, and the recursive subdivision of the Hamiltonian – only the first two are strictly necessary to the resulting algorithm. The major benefit of the recursion is that it pushes the transitions entirely into the kick operators and preserves the ability to apply the drift operator merely by solving Kepler's equation, albeit at the cost of considerable complexity. If we surrender this requirement, however, then we can decompose the Hamiltonian into three terms

$$H = H_{\text{Sun}} + [F(i, j) H_{i,j}] + [(1 - F(i, j)) H_{i,j} + H_{\text{Kep}}] \quad (16)$$

where $H_{i,j}$ is the component of H_{int} involving objects i and j , with implied summation over all i, j with $i < j$. $F(i, j)$ is a transition function which is 1 when the objects are distant and approaches 0 when they are undergoing an en-

counter. As in the basic DH step (eq. 14), this decomposition gives rise to a five-operator step, but these are the only five terms to consider, unlike the much larger number of potentially active terms in eq. 15. It is true that whenever an encounter is occurring and $F(i, j)$ could be nonzero then the interaction terms can no longer be advanced analytically, but they can still be numerically integrated to high precision using standard techniques such as Bulirsch-Stoer. Moreover, and this advantage should not be underestimated, testing that the above algorithm is implemented correctly is far more straightforward than testing SyMBA. Whenever the cost of the numerical integration due to encounters is a small fraction of the computation, the Chambers-style approach (although perhaps not as elegant as SyMBA itself) is likely preferable on pragmatic grounds. It should also be noted that despite the use of numerical integration to handle the transition-weighted terms in the Hamiltonian, the mapping itself remains symplectic; or as symplectic as any floating-point implementation of sufficient precision can be. (See Skeel 1999 for a general technique to recover symplecticity when using otherwise non-symplectic approximations.)

2.3 Close encounters with the Sun

In any case, both SyMBA and the Chambers variant have been successfully applied to many studies of the later stages of planet formation. Their chief weakness is that neither can easily deal with objects undergoing close encounters not with each other but with the Sun, such as high-eccentricity Sun-grazing comets. Unlike the case of mutual encounters in which the important terms are H_{int} and H_{Kep} , during a close solar passage H_{Sun} must be evaluated more frequently. Therefore, to resolve such orbits correctly, one must choose a timestep small enough to resolve the pericentre passage, and that timestep must be fixed for the entire integration, even if such encounters are very rare. To overcome this limitation, Levison & Duncan (2000) added a Chambers-style splitting on top of SyMBA (here we suppress the planetary encounter terms, which are handled as described before) and use

$$H^\tau = (1 - F) H_{\text{Sun}}^{\tau/2} + H_{\text{int}}^{\tau/2} + (F H_{\text{Sun}} + H_{\text{Kep}})^\tau + H_{\text{int}}^{\tau/2} + (1 - F) H_{\text{Sun}}^{\tau/2} \quad (17)$$

$$H = (1 - F) H_{\text{Sun}} + H_{\text{int}} + (F H_{\text{Sun}} + H_{\text{Kep}}) \quad (18)$$

where F is a transition function which is 0 when no object is near the Sun and 1 when *any* object is. In this scheme, when any object is undergoing a close solar approach, then the work of performing an integration step is pushed into the new Kepler step which is must be handled numerically. The non-separability of H_{Sun} – i.e. the inability to isolate an individual object as in H_{Kep} – becomes a serious inconvenience here, as it requires the numerical integration of every object in the system even if only one object enters the inner zone. Nevertheless, as explained by Levison & Duncan (2000), this approach provides the speed of SyMBA whenever the inner regions are empty and yet can successfully survive occasional interlopers (such as objects due to be ejected during violent periods in the formation process).

This method cannot be directly applied as a solution for the numerical challenge of hot exoplanet formation. If we set the inner boundary at a typical terrestrial-formation value like 0.5 AU, then there will usually be many, and almost always be some, protoplanets and planetesimals in the innermost region. This means that every particle's H_{Kep} will be numerically integrated on every step, and the speed benefits are lost. Moreover, if there are mutually-gravitating objects inside the inner boundary, then the situation is worse: the above integrator will evaluate the interactions between bodies not undergoing close encounters on the outer timestep τ , which may bear little relation to the dynamical times for the inner objects. This particular problem could be corrected by bringing H_{int} under the transition function F as well, but then we have merely recovered – in an impressively roundabout fashion – a Bulirsch-Stoer integrator.

2.4 Individual timesteps

Recognizing that in an MVS integration of the solar system, one is taking hundreds of times more steps per Pluto orbit than would be necessary if not for the presence of the interior planets, Saha & Tremaine (1994) construct a leapfrog integrator with individual timesteps. They split H_{Kep} and H_{int} into N terms each, such that

$$H_{\text{Kep}} = \sum_{i=1}^N H_{\text{Kep},i}, \quad H_{\text{int}} = \sum_{i=1}^N H_{\text{int},i} \quad (19)$$

where $H_{\text{Kep},i}$ is the Kepler term for planet i (with objects labelled in increasing semimajor axis), and $H_{\text{int},i}$ is the interaction term between planet i and planets $i+1$ through N . Translating into our notation, we use D_i and K_i to refer to the operators as before, and assign a timestep τ_i to each planet, where the largest timestep $\tau = \tau_N$ and $\tau_{i+1}/\tau_i = M_i$ for M_i an integer. Starting with the Hamiltonian only involving the outermost planet (note that K_N is the identity operator):

$$H^\tau \approx D_N^{\tau_N/2} K_N^{\tau_N} D_N^{\tau_N/2} \quad (20)$$

and recursively applying

$$K_i^\tau \rightarrow [D_{i-1}^{\tau_{i-1}/2} K_{i-1}^{\tau_{i-1}} K_i^\tau D_{i-1}^{\tau_{i-1}/2}]^{M_{i-1}} \quad (21)$$

for $i > 1$, one obtains an N -level integrator. More concretely, consider a two-planet case with timestep ratios of 1:3. The resulting integrator (after removing the K_2 term which does nothing)

$$H^\tau \approx D_2^{\tau_2/2} [D_1^{\tau_1/2} K_1^{\tau_1} D_1^{\tau_1/2}]^3 D_2^{\tau_2/2} \quad (22)$$

has a timestep of τ_1 for the inner planet, and τ_2 for the outer planet, as desired. Note that the integrator is time-reversible even though the objects are not synchronized with respect to D when the interaction term K_1 is applied. (Also note that in practice one would combine neighbouring D_1 terms.)

It is important to recognize that the timesteps associated in this method are individual but not adaptive; they must be set at the start of the integration, and attach not to spatial zones but directly to objects. It is therefore unable to handle migrating objects, and as an MVS method inherits the previously mentioned weaknesses of Jacobi coordinates for our purposes. However, it demonstrates that

asynchronous multi-stage integration in MVS-like contexts can be constructed.

2.5 Constructing the new integrator

We now have the necessary ingredients to construct a symplectic integrator, Naoko (“New Adaptive Orthochronous Kepler Orbiter”), which is Kepler-adapted, close-encountering, and yet allows for zones with different timesteps. Recall the basic DH step:

$$H^\tau \approx L^{\tau/2} K^{\tau/2} D^\tau K^{\tau/2} L^{\tau/2} \quad (23)$$

We will seek a generalization of this step for the multiple-zone case. We will define our timestep zones by dividing the system into radial shells such that an object’s instantaneous heliocentric radius determines its zone assignment. (This definition is mentioned here for concreteness; other choices are possible. We motivate this particular choice in §2.6.) We label the zones using integer indices, starting at 0 for the innermost zone, and an integer subscript on an operator corresponds to the operator for that zone, in a sense which will be made explicit later. For example, D_0^τ advances all objects in zone 0 for a timestep τ under H_{Kep} but does nothing to objects in other zones: the commutator bracket $[D_i, D_j] = 0$. Note that this differs from the Saha & Tremaine (1994) usage of subscripts to refer to planets.

To begin with, we defer consideration of interactions between the planets. Under this simplification, and starting with zone 1, eq. 23 becomes

$$H^\tau \approx L^{\tau/2} D_1^\tau L^{\tau/2} \quad (24)$$

The L terms cannot be divided into zones as H_{Sun} is not separable. Nevertheless, we can incorporate more zones by applying the individual-leapfrog approach of Saha & Tremaine (1994) and recursively subdividing the L steps using this expression. That is, we can write

$$L^{\tau/2} \rightarrow L^{\tau/4} D_0^{\tau/2} L^{\tau/4} \quad (25)$$

resulting in

$$H^\tau \approx \left[L^{\tau/4M_0} D_0^{\tau/2M_0} L^{\tau/4M_0} \right]^{M_0} D_1^\tau \left[L^{\tau/4M_0} D_0^{\tau/2M_0} L^{\tau/4M_0} \right]^{M_0} \quad (26)$$

where M_0 is an integer setting the number of zone 0 steps per zone 1 step.

This integrator looks promising. In the absence of any objects in zone 1, this is merely $2M_0$ (kick-free) DH steps of size $\tau/2M_0$ next to each other, and in the absence of any objects in zone 0, the D_0 operators do nothing and the L operators collapse, reducing to a DH step of size τ . There are $2M_0$ zone 0 drifts per zone 1 drift, so if we assume each drift takes equal time then if $N_1 > 2M_0N_0$, the zone 1 computation dominates. As long as $N_1 \gg 2M_0N_0$, then handling objects in the innermost zone – far from requiring a major decrease in system timestep as in the standard approach – is effectively free; and, importantly, they can be handled independently of the outer objects.

Despite appearances, the presence of the L terms on the smallest timescale does not remove this separability.

Although L must be formally *applied* with the innermost timestep, this does not mean that L must be *computed* at that frequency. Since D_0 does not affect objects in zone 1, and L changes their positions but not their velocities, we need only determine their contribution to L at the beginning of the zone 0 substep, and we can delay actually moving them until the beginning of the zone 1 substep. Implementing a lazy-evaluation scheme is relatively simple. (Since L is so trivial to evaluate and apply, it is seldom a bottleneck, at least in the serial case. For parallel implementations, we find that lazy evaluation is vital, because otherwise the communication overhead involved produces enormous scaling difficulties. Potential implementors should bear this warning in mind when designing data structures.)

One can easily generalize to more zones. The three-zone case is the simplest integrator where the transition functions we will develop can be carried through to a larger number of zones, and therefore we will use it as our standard example. In a minor abuse of notation, define $S^\tau = L^{\tau/2} D^\tau L^{\tau/2}$ (note that unlike with L , D , and K , $[S^\tau]^M \neq S^{M\tau}$.)

Then we have the two-zone integrator

$$H^\tau = \left[S_0^{\tau/2M_0} \right]^{M_0} D_1^\tau \left[S_0^{\tau/2M_0} \right]^{M_0} \quad (27)$$

and the three-zone version

$$H^\tau = \left[\left[S_0^{\tau/4M_0M_1} \right]^{M_0} D_1^{\tau/2M_1} \left[S_0^{\tau/4M_0M_1} \right]^{M_0} \right]^{M_1} D_2^\tau \left[\left[S_0^{\tau/4M_0M_1} \right]^{M_0} D_1^{\tau/2M_1} \left[S_0^{\tau/4M_0M_1} \right]^{M_0} \right]^{M_1} \quad (28)$$

where M_i sets the number of zone i substeps per zone $i+1$ step.

After one step, objects in all zones have been advanced the correct total time under each operator. Moreover, neglecting the influence of objects in other zones, each zone has experienced what is locally a standard DH step: objects in zone 0 took a timestep of $\tau/4M_0M_1$; objects in zone 1 had a timestep of $\tau/2M_1$; and objects in zone 2 had a timestep of τ .

We must now choose where to place the force operators. To simplify the discussion, we set $M_0 = M_1 = 1$, and assume that the zones are separated such that τ , $\tau/2$, and $\tau/4$ are appropriate DH timesteps for all objects in the respective zones; recovering the general case is straightforward. The kick-free three-zone integrator is given by

$$H^\tau = L^{\tau/8} D_0^{\tau/4} L^{\tau/8} D_1^{\tau/2} L^{\tau/8} D_0^{\tau/4} L^{\tau/8} D_2^\tau L^{\tau/8} D_0^{\tau/4} L^{\tau/8} D_1^{\tau/2} L^{\tau/8} D_0^{\tau/4} L^{\tau/8} \quad (29)$$

Let K_{ij} be the kick operator between zones i and j . In order to treat close encounters using the Chambers splitting, we must have each D_i surrounded by two K_{ii} .

$$H^\tau = L^{\tau/8} K_{00}^{\tau/8} D_0^{\tau/4} K_{00}^{\tau/8} L^{\tau/8} K_{11}^{\tau/4} D_1^{\tau/2} K_{11}^{\tau/4} L^{\tau/8} K_{00}^{\tau/8} D_0^{\tau/4} K_{00}^{\tau/8} L^{\tau/8} K_{22}^{\tau/2} D_2^\tau K_{22}^{\tau/2} L^{\tau/8} K_{00}^{\tau/8} D_0^{\tau/4} K_{00}^{\tau/8} L^{\tau/8} K_{11}^{\tau/4} D_1^{\tau/2} K_{11}^{\tau/4} L^{\tau/8} K_{00}^{\tau/8} D_0^{\tau/4} K_{00}^{\tau/8} L^{\tau/8} \quad (30)$$

This integrator does not incorporate interzone forces, but intrazone forces are evaluated on the appropriate timescale

relative to the drift timescale for objects in that zone. One can therefore apply the Chambers-style encounter handling between the sets of $K_{ii}D_iK_{ii}$ as described in section 2.2 and we recover the standard approach. (In some situations we have found the *DKD* operator splitting is superior, but for reasons involving implementation details we will restrict ourselves to discussing the *KDK* version.)

There are many possible arrangements for force communication between zones. We optimistically choose the scheme requiring the fewest force calculations, and update forces between zones i and j on the outermost zone's timestep. This choice results in

$$H^\tau = \begin{aligned} & L^{\tau/8} K_{00}^{\tau/8} D_0^{\tau/4} K_{00}^{\tau/8} L^{\tau/8} \\ & K_{01}^{\tau/4} K_{11}^{\tau/4} D_1^{\tau/2} K_{11}^{\tau/4} K_{01}^{\tau/4} \\ & L^{\tau/8} K_{00}^{\tau/8} D_0^{\tau/4} K_{00}^{\tau/8} L^{\tau/8} \\ & K_{02}^{\tau/2} K_{12}^{\tau/2} K_{22}^{\tau/2} D_2^{\tau/2} K_{22}^{\tau/2} K_{12}^{\tau/2} K_{02}^{\tau/2} \\ & L^{\tau/8} K_{00}^{\tau/8} D_0^{\tau/4} K_{00}^{\tau/8} L^{\tau/8} \\ & K_{01}^{\tau/4} K_{11}^{\tau/4} D_1^{\tau/2} K_{11}^{\tau/4} K_{01}^{\tau/4} \\ & L^{\tau/8} K_{00}^{\tau/8} D_0^{\tau/4} K_{00}^{\tau/8} L^{\tau/8} \end{aligned} \quad (31)$$

This approach succeeds in separating the integration of zone i objects from zone j objects. Objects in zone 2 need only have drifts and kicks involving them evaluated on the timestep τ ; objects in zone 1 on $\tau/2$; and zone 0 on $\tau/4$; and as already discussed L is not a problem. Note that the above integrator was built to minimize the number of force operators, but one could evaluate the cross-zone kicks (K_{12} , for example) more frequently if desired.

The above integration technique obeys Newton's third law regarding interparticle forces. Although forces between objects in different zones are computed less frequently than forces within a zone, whenever gravitational accelerations are computed between two bodies the accelerations are equal and opposite (even for close-encountering objects in a transition zone, to be discussed later) and they are immediately applied and turned into changes in velocity. No force lag or accumulation is involved.

2.6 Transition functions

We recall that the key insight of DLL98 is that to preserve symplectic behaviour while effectively changing the integration step (and therefore the surrogate Hamiltonian) an object must experience a smooth transition from one integration regime to another. Roughly speaking, if an object's transition is sufficiently smooth, then instead of suddenly finding itself evolving under a different surrogate Hamiltonian, it believes it is merely in a different regime of the original Hamiltonian. Accordingly, we now return to the previously-deferred issue of choosing appropriate transition functions, which turns out to be the most challenging part of the problem.

Let $f(x)$ be a switch function, a real-valued nondecreasing function defined on $[0, 1]$ with $f(0) = 0$ and $f(1) = 1$. We take the extension outside this domain (equal to 0 below and 1 above) as given, under which convention $f(x) = x$ is a switch. The simplest switch is a shifted step function:

$$f_{\text{step}}(x) = \begin{cases} 0 & x < 1 \\ 1 & x \geq 1 \end{cases} \quad (32)$$

However, this leads to sudden movement of portions of the




Figure 1. Various candidate switch functions, discussed in §2.6.

Hamiltonian from one term to another, and symplecticity is lost. DLL98 suggest

$$f_{\text{DLL3}}(x) = 3x^2 - 2x^3 \quad (33)$$

as one of their switches, which has $f'(x) = 0$ at both endpoints, as well as the higher-order

$$f_{\text{DLL7}}(x) = x^4(35 - 84x + 70x^2 - 20x^3) \quad (34)$$

Chambers (1999) suggests

$$f_{\text{Ch}}(x) = x^2/(2x^2 - 2x + 1) \quad (35)$$

as a useful compromise between smoothness and efficiency of evaluation. Rauch & Holman (1999) prefer

$$f_{\text{RH}}(x) = \frac{1}{2} \left(1 + \tanh \left[\frac{2x - 1}{x(1 - x)} \right] \right) \quad (36)$$

for which all derivatives vanish at the endpoints. Figure 1 shows the various functions. We will use the cubic polynomial switch f_{DLL3} , but the construction is independent of this choice. (This issue is discussed further in §3.1.1.)

To reduce clutter we define a rescaling function on the switch,

$$C(x, x_0, x_1) = f_{\text{DLL}} \left(\frac{x - x_0}{x_1 - x_0} \right) \quad (37)$$

and build our transition functions from this base.

As described briefly in §2.5, we divide the system into zones based on instantaneous heliocentric radius r , and imagine a set of spherical shells around the Sun. Each zone has a transition region near the interior and exterior edge of the shell in which operators involving both adjacent zones will act on an object. Let R_i be the locations of the i zone boundaries and $2h_i$ be the widths of the transition regions, as illustrated in figure 2.

An unfortunate consequence of this choice is that the resulting evolution of transiting objects under D is no longer analytically integrable. It is tempting to construct a transition function based not on r but on the osculating semi-major axis a , which is constant during D and can therefore be used (along with all other orbital elements save those




Figure 2. A sketch of the radial zone scheme.

such as the mean anomaly describing the position along the orbit) to build a weighted but integrable D . Indeed, experiments show that an a -based function can work for isolated objects in the transition region. However, doing so vastly complicates the treatment of close encounters, as two encountering objects must have similar instantaneous r but can have very different a : consider a high- e zone 0 object at apocentre meeting a high- e zone 1 object at pericentre. Under an r -based weighting scheme, the difference in their effective drift timestep is bounded by their physical radial separation which gets smaller as the encounter gets deeper, whereas under an a -based scheme the drift timestep experienced by the inner object could remain very different from that of the outer object, which is not a recipe for numerical stability. A function which smoothly changes dependence from r to a with changes in the encounter status may be possible, but in our view the potential benefits are outweighed by the resulting complexity.

For the integrators presented here, such as that of eq. 31, there are three types of transitions we must consider: (1) those involving drifts; (2) those involving distant kicks; and (3) those involving close encounters. Each has its own peculiarities, and treating (2) and (3) simultaneously is rather awkward.

2.6.1 Drift transitions

The drift transitions are the easiest to handle. We need a function which will yield (for example) the full D_1 term for an object completely within zone 1, and likewise with D_2 and an object in zone 2, but which will return smoothly-varying intermediate values for objects inside the transition zones $[R_1 - h_1, R_1 + h_1]$ and $[R_2 - h_2, R_2 + h_2]$, and generally $[R_i^-, R_i^+]$ where $R_i^\pm \equiv R_i \pm h_i$. (For simplicity we will restrict ourselves to considering symmetric functions, although since objects in inner zones will have higher velocities and different effective timesteps, it is possible that an asymmetric function could yield better results.) Such a function is given by

$$W_D(r, i) = \begin{cases} 0 & r \leq R_i^- \\ C(r, R_i^-, R_i^+) & R_i^- \leq r \leq R_i^+ \\ 1 & R_i^+ \leq r \leq R_{i+1}^- \\ 1 - C(r, R_{i+1}^-, R_{i+1}^+) & R_{i+1}^- \leq r \leq R_{i+1}^+ \\ 0 & R_{i+1}^+ \leq r \end{cases} \quad (38)$$

where r is the instantaneous heliocentric radius and i is the zone index. This is nothing more than a SyMBA-style transition applied to r instead of to the interplanet separation. Although in general each R_i can have an associated transition zone, in practice the boundary ‘transitions’ are slightly degenerate. Typically one would set the inner transition region, (R_0, h_0) , and the outer transition region, here (R_3, h_3) , well outside the radii of interest so that the sum of weights over all zones is equal to 1 for all integrated objects regardless of r . In practice we make R_0 smaller than our inner edge (set by the physics of the problem or the numerics of our timestep), R_3 larger than the outer edge, and let h_0 and h_3 be some arbitrary small distance. Figure 2 sketches the resulting scheme, with three timestep zones and effectively two (not four) transition zones.

2.6.2 Distant forces

Treating the forces is more difficult, as it involves not only the interacting bodies’ two distinct orbital radii but the separations between them. We seek a function which will ensure the objects experience sufficient continuity in their forces as they move from zone to zone. We will first consider only distant forces (i.e. we imagine all forces are ‘soft’, requiring no special attention) and then correct to handle close encounters.

Consider an integrator with three zones, labelled i , j , and k from innermost to outermost, and two planets, with orbital radii r_0 and r_1 . Let the objects start in the zone j . Initially, all the weight should be in K_{jj} . If we keep $r_0 = r_1$ and move the pair together both inwards and outwards, we see that we need smooth transitions between K_{ii} and K_{jj} as well as between K_{jj} and K_{kk} . If we instead keep r_0 constant while increasing r_1 , then as the second object crosses from j to k , then the K_{jj} weight must decrease and K_{jk} must increase until r_1 is fully within k and the K_{jk} weight is 1. If we decrease r_0 and increase r_1 , then when both objects are in the centre of the transition zones (i - j and j - k), we will need to spread the force out over four different terms: K_{ij} , K_{jk} , K_{ik} , and K_{jj} .

This can be achieved by symmetrizing W_D :

$$W_{\text{dist}}(r_0, r_1, i, j) = \begin{cases} (W_D(r_0, i) W_D(r_1, j) + W_D(r_1, i) W_D(r_0, j))/2 & i = j \\ W_D(r_0, i) W_D(r_1, j) + W_D(r_1, i) W_D(r_0, j) & i \neq j \end{cases} \quad (39)$$

2.6.3 Close encounters

Now we must ensure that close encounters are correctly shared. This requires a transition function W_{cl} which will move the force between two objects from the K_{ii} term to the D_i term as in the Chambers methods, resulting in a triplet of terms

$$\left[\frac{1}{2} W_{\text{cl}} K_{ii} \right] + [(1 - W_{\text{cl}}) K_{ii} + D_i] + \left[\frac{1}{2} W_{\text{cl}} K_{ii} \right] \quad (40)$$

eq. 16. We take

$$W_{\text{cl}} = C(ds, ds_{\text{crit}}/2, ds_{\text{crit}}) \quad (41)$$

where ds_{crit} , after DLL98, is several times the sum of the Hill radii (with a possible additional dependence on orbital velocity; as Chambers has noted, what matters is ensuring you integrate through the transition.) Note that unlike the transition function recommended in Chambers (1999), W_{cl} moves all of the encounter into the numerically-integrated term $(1 - W_{\text{cl}})K_{ii} + D_i$ at separation $ds = ds_{\text{crit}}/2$, not at $ds = 0$.

2.6.4 Combining the transitions

Each of the three above transition functions – W_D , which applies to the D operators; W_{dist} , which applies to all K_{ij} operators; and W_{cl} , which applies between K_{ii} operators – makes sense independently. The natural way to combine them would give (for example, suppressing indices on the transition functions):

$$\frac{(W_{\text{dist}}K_{23})^{\tau_3/2} (W_{\text{dist}}W_{\text{cl}}K_{33})^{\tau_3/2}}{[W_{\text{dist}}(1 - W_{\text{cl}})K_{33} + W_D D_{33}]^{\tau_3}} \quad (42)$$

$$(W_{\text{dist}}W_{\text{cl}}K_{33})^{\tau_3/2} (W_{\text{dist}}K_{23})^{\tau_3/2}$$

The above approach has a minor problem, however. Consider two objects undergoing an encounter in a transition zone (say, the i - j boundary.) The above functions will attempt to share force across three terms: K_{ii} , K_{jj} , and the cross-term K_{ij} . However, the integrator is only built to treat the encounter using the $K_{ii}D_iK_{ii}$ and $K_{jj}D_jK_{jj}$ substeps. Any force that the K_{ij} operator is assigned is only sampled on the larger timestep, and if the two objects are both in the middle of the transition zone this can be as much as half the total force. This will result in a highly inaccurate integration.

How can this be repaired? In the case of an encounter, K_{ii} and K_{jj} should share all the force:

$$W_{\text{near}}(r_0, r_1, i, j) = \begin{cases} (W_D(r_0, i)W_D(r_1, j) + W_D(r_1, i)W_D(r_0, j))/2 & i = j \\ 0 & i \neq j \end{cases} \quad (43)$$

In the absence of encounters, the above method (eq. 42) should work. Therefore we define yet another transition function,

$$W_{\text{shift}} = C(ds, ds_{\text{crit}}, 2ds_{\text{crit}}) \quad (44)$$

and use it to smoothly interpolate between the no-encounter case when all operators are involved and the encounter case when only the intrazone operators share the force. (Here we will require that objects cannot undergo mutual encounters unless they are in neighbouring zones. Removing this limitation is possible but unnecessary for our intended applications.) Combining the above, we write

$$W_K(i, j) = W_{\text{shift}}W_{\text{dist}} + (1 - W_{\text{shift}})W_{\text{near}} \quad (45)$$

and replace instances of W_{dist} with this encounter-corrected expression.

2.7 Assembling the integrator

The final integrator is constructed by applying the drift transition function (eq. 38) and the kick transition function

(eq. 45) to the multilevel step of eq. 31. The order of the substeps and the relationships between the τ_l are determined by the recursive subdivision of eq. 21 (as in eq. 31). For each substep of level l , the algorithm proceeds as follows:

- (1) Do the linear drift: if $l = 0$, apply L_0 for $\tau_0/2$.
- (2) Apply the distant forces between l and all interior levels: apply $W_K(i, l)W_{\text{cl}}K_{il}$ for all $i \leq l$ for $\tau_l/2$.
- (3) Drift (including possible encounters): apply the distant forces between l and all interior levels: apply $W_K(l, l)(1 - W_{\text{cl}})K_{ll} + D_l$ for τ_l . (Note that any implementation would avoid doing this numerically when the kick term was known to be zero because the objects are too well-separated.)
- (4) Apply the distant forces between l and all interior levels: apply $W_K(i, l)W_{\text{cl}}K_{il}$ for all $i \leq l$ for $\tau_l/2$.
- (5) Do the linear drift: if $l = 0$, apply L_0 for $\tau_0/2$.

A moment's consideration confirms that as promised in §1, this is nothing more than the step subdivision of Saha & Tremaine (1994) applied to the Hamiltonian of DLL98 with the close encounter handling of Chambers (1999), with staggered force calculations, and some new transition functions incorporated to ensure smoothness.

In practice, we do not use the above scheme directly, but instead use a ‘lower-level’ scheme (motivated in part by Rauch & Holman 1999) in which we do not apply the transitions between terms in the Hamiltonian but between the resulting $\partial q/\partial t$ and $\partial p/\partial t$. That is, given two pieces of the Hamiltonian H_A and H_B and a transition function $f = f(q)$ between them, instead of starting with the decomposition

$$[fH_A] + [(1 - f)H_A + H_B] \quad (46)$$

which produces

$$\frac{dq}{dt} = \frac{\partial}{\partial p}(fH_A), \quad \frac{dp}{dt} = -\frac{\partial}{\partial q}(fH_A) \quad (47)$$

$$\frac{dq}{dt} = \frac{\partial}{\partial p}((1 - f)H_A + H_B), \quad \frac{dp}{dt} = -\frac{\partial}{\partial q}((1 - f)H_A + H_B)$$

as the derivatives to be integrated, we write

$$\frac{dq}{dt} = f \frac{\partial H_A}{\partial p}, \quad \frac{dp}{dt} = -f \frac{\partial H_A}{\partial q} \quad (48)$$

$$\frac{dq}{dt} = (1 - f) \frac{\partial H_A}{\partial p} + H_B, \quad \frac{dp}{dt} = -(1 - f) \frac{\partial H_A}{\partial q} + H_B$$

and apply the transition directly between the derivatives themselves. This saves some computation (of the cross-terms $H\partial f/\partial q$, at least; the $H\partial f/\partial p$ terms are all 0 because f is not a function of the momenta) and increases the effective smoothness of the transition for a fixed f because one does not lose a degree of smoothness passing from H to its derivatives. It might be objected that this means the resulting integration technique is no longer strictly symplectic, but in fact one can construct a Hamiltonian (admittedly somewhat artificial) for which an obviously symplectic integrator generates exactly this algorithm. However, even if this were not the case and we were to view the integrator as merely ‘near-symplectic’, it remains time-reversible and works well in practice, which agrees with the results of Rauch & Holman (1999) who applied the transition functions in their SyMBA-style decomposition to the forces and not the potential. Of course, one may work with the original Hamiltonian-level splitting if preferred.

One easily overlooked issue which is only apparent when considering a global simulation is that in the SyMBA scheme

the (effective) Hill radii – the Hill radii used in the close encounter criteria – are fixed at the start of the integration. This is necessary to ensure that the integration remains both symplectic and analytically soluble. However, in cases where there is considerable inward migration, an object will have an unnecessarily large close encounter criterion when it arrives at the inner portion of the disc. Similarly, an outward migrating object could miss encounters. The strict solution is to bring the Hill radius dependence of the close encounter weight function under the numerical integration; the lazy not-quite-symplectic solution is to update the effective Hill radii on some interval, at the risk of interfering with ongoing encounters. All things being equal, if the system is messy and the number of updates is low it is unlikely to make a statistically significant difference.

3 TESTS OF THE METHOD

The algorithm was implemented using the existing codebase of *miranda* (McNeil 2006) as a framework, and using a standard Bulirsch-Stoer routine to handle the numerically integrated terms in the Hamiltonian. Since the method reduces to the well-understood Chambers approach in the one-zone limit, we will concentrate on testing the performance of the multiple-zone aspects of the code. We have confirmed by comparison with *miranda* in both SyMBA and Bulirsch-Stoer modes that the new code behaves as expected in the one-zone case. Unless otherwise specified, the numerical integration tolerances were set at 10^{-16} (which in practice generates errors $\sim 10^{-14}$). The radial-transition detection routine numerically integrates an object if its osculating orbit as determined on the outer step comes within 5% of the transition zone.

3.1 Single planet

Here we consider a two-zone integrator with outer timestep 0.05 yr and inner timestep 0.025 yr. First we set the transition zone from 0.9 to 1.1 AU. We place objects of masses ranging from $1 M_{\oplus}$ to $10000 M_{\oplus}$ at semimajor axes between 0.8 and 1.2 AU, and consider the resulting behaviour of the energy (in the one-planet case, a measure of the variation in semimajor axis). For objects which enter the transition region, the surrogate Hamiltonian under which the planet is moving contains terms from both the inner and outer zones.

Figure 3 shows three points for each of the five mass cases (1, 10, 100, 1000, and $10000 M_{\oplus}$) at each initial semimajor axis: one for the basic DH integrator (eq. 14) with a timestep of 0.025 yr, one for Naoko, and one for the DH integrator with a timestep of 0.05 yr. The errors generally decrease with increasing semimajor axis: for a fixed timestep, at larger orbital radius there are more steps per orbit. As expected, for objects in the transition zone, the new code reports errors which smoothly interpolate between those of the smaller and larger DH runs, and become indistinguishable from the standard algorithm outside the transition region. In the $10000 M_{\oplus}$ runs – 3% of the mass of the Sun – there are some slight deviations apparent at the edges of the transition region. The clean interpolation also breaks down at very low mass for a different reason: the integration error is dominated by the integration tolerance.




Figure 3. Energy error as function of semimajor axis and object mass; the DH runs for 0.025 and 0.05 yr timesteps are in green, the Naoko runs are in blue.




Figure 4. Maximum eccentricity as function of semimajor axis and object mass. Most of the $1 M_{\oplus}$ runs are not plotted, as their maximum e was 0.

The situation is very similar for the eccentricities, as shown in figure 4. Again we see the new code interpolating between the 0.05 and 0.025 yr DH runs. This shows that at least in a sufficiently smooth case, integrating an isolated object on multiple timesteps need not introduce spurious energy or angular momentum behaviour.

Figure 5 shows the relative energy error as a function both of the timestep and the inner:outer timestep ratio, where the largest outer timestep used was 0.05 yr, for a $1 M_{\oplus}$ object at 1 AU with $e = 0.1$, with transition zone from 0.95–1.05 AU. As expected, the integrator behaves as a second-order algorithm. Increasing the ratio to take more




Figure 5. Maximum relative energy error as function of timestep and inner:outer timestep ratio for a $1 M_{\oplus}$ object at 1 AU with $e = 0.1$, with transition zone from 0.95-1.05 AU.

inner steps per outer step improves the energy error very little beyond 4:1, as the maximum error is controlled by the outer step which is not changing.

Although this condition is necessary, it is clearly insufficient. More realistic tests involve objects which repeatedly cross from the inner zone to the outer zone through the transition zone during the same orbit.

Without loss of generality we placed a $1 M_{\oplus}$ object in the centre of a transition zone at 1 AU, and varied both the eccentricity e and the relative transition zone half-width h , where h is defined so that the zone extends from $a(1-h)$ to $a(1+h)$, in analogy with the eccentricity. The outer timestep was chosen to be 1/20th of the orbital period, the eccentricities were varied from 0.001 to 0.37 (the latter chosen because that corresponds to a perihelion for which 0.025 yr is 1/20th of the orbital period at that distance), and the half-width was varied from 0.01 to 0.50 AU. The resulting maximum relative energy error is shown in figure 6 as a function of the e/h ratio; the contours correspond to constant e .

At small e/h – that is, when the transition zone is larger than or comparable to the radial excursion per orbit – the energy error is well-behaved for a fixed e , and is only weakly dependent on h . At $e/h \gtrsim 10$, there are many integrations which do not converge. Nonconvergence is easily recognized from the evolution of the semimajor axis or the eccentricity: the planet begins to migrate away from its original location until it finds a semistable configuration. Examples are given in figure 7 for $e \simeq 0.25$. Not only does the transition need to be sufficiently smooth along an orbit, but for a run with a larger tolerance or a larger timestep, a wider transition zone may be required so that the numerical integrator can detect the transition (unless the code accepts hints about the location of difficulties in the integrand).




Figure 6. Maximum relative energy error as a function of transition width and eccentricity; the eccentricity increases between curves by a factor of 1.48.




Figure 7. Relative change in semimajor axis and eccentricity for various transition half-widths h at $e \simeq 0.25$; the three half-widths below did not converge.

3.1.1 Varying the switch

We also explored the effects of alternate choices of transition function. We place a $1 M_{\oplus}$ object at 1 AU with $e = 0.2$, and a transition zone extending from 0.95 to 1.05 AU with, with outer timestep 0.05 yr and inner timestep 0.025 yr. We then vary the switch over the six functions described in §2.6: the step function; the switch $f(x) = x$; the DLL98 cubic; the DLL98 septic; the Chambers switch; and the Rauch & Holman switch. Figure 8 shows the resulting relative en-




Figure 8. Maximum relative energy error for single planet at 1 AU, $e=0.2$, with transition zone 0.95-1.05 AU, for various switch functions.

ergy errors: the behaviours for the convergent integrations continue for millions of orbits.

The step function fails immediately: the object migrates outward in semimajor axis to ~ 1.00456 AU over the first 2700 years and then stops, corresponding to a maximum relative energy error of ~ 0.0046 . The remaining integrations all succeeded, with f_{DLL3} showing the smallest energy error and f_{RH} the largest. We have found this is typical. That the crude f_X performs better than the smooth f_{RH} can be understood by returning to figure 1: f_{RH} is the smoothest function, but for a fixed transition width it is also the one with the narrowest effective transition (extending roughly from $x=0.25$ to $x=0.75$).

The execution times for the various switches (excluding the step function) were generally comparable – mostly agreeing within the scatter – except that the Rauch & Holman switch was consistently the slowest, and f_X the fastest. The slower speed of the RH switch is likely chiefly due to the evaluation of the trigonometric function. (Note that some versions of the common GCC C compiler will occasionally refuse to inline functions for obscure reasons, leading to strange profiling results.)

Thus we chose f_{DLL3} as the best compromise between efficiency of evaluation and energy conservation.

3.2 Multiple planets

The above results are unsurprising, insofar as the use of smooth transitions to move portions of the Hamiltonian from one part of the step to another is familiar. Of more concern is whether the reduction in the number of force evaluations will lead to unacceptable resolution of the angular momentum exchange between planets in different zones. We will concentrate on the interactions which are likely to be

the most sensitive to changes in sampling frequency, namely resonant interactions. Recall that we are willing to accept a cruder approximation to the dynamics than we would ordinarily do, as long as there are no clear integration failures. Since one of our interests is studying migration scenarios, in which resonances play a significant role, it is important to verify that such behaviour is not lost when using the multi-zone methods.

We will verify that resonant behaviour can persist when the objects are in different zones, when one object is in a transition zone, and when the objects migrate across a zone in resonance (coorbital or otherwise). In each simulation we have used the two-zone 0.05/0.025 yr 0.9-1.1 AU transition. To make comparisons with the behaviour of the DH integrator clearer we have disabled the encounter treatment for the following sections (until §3.2.7).

3.2.1 2:1 mean motion resonance

We place two $2 M_{\oplus}$ objects on cold $e \sim 0.002$, $i \sim 0$ orbits in the 2:1 mean motion resonance in three configurations: (1) $a_1 = 0.63$ AU, $a_2 = 1.00$ AU, where the outermost object is in the middle of the transition region; (2) $a_1 = 0.76$ AU, $a_2 = 1.20$ AU, where neither object is in the transition zone but the objects are in different zones; and (3) $a_1 = 1.00$ AU, $a_2 = 1.59$ AU, where the innermost object is in the transition zone. (All semimajor axes are approximate; the initial configurations were found by introducing a slowly-decreasing dissipation into the DH algorithm.) The evolution of the resonance angles is plotted in figure 9. In all cases the resonance is preserved, and in the cases where one object was in a transition zone the agreement is excellent between the Naoko results and the results of a DH run with timestep 0.025 yr. In the second case – in which neither object is in a transition zone – the libration is considerably larger in the Naoko run. This is not surprising: in the absence of dissipation the resonance is quite sensitive to the initial conditions, and case 2 has the greatest sudden change from DH to Naoko, as none of the force is being evaluated on the higher (inner) frequency. Even in this case, the introduced libration is comparable to the differences in width between different DH runs in which only the initial angles had been changed. For our purposes it is sufficient that the objects remain resonant, which they do.

3.2.2 Co-orbitals

We place two objects – one $10 M_{\oplus}$ and one $1 M_{\oplus}$ – at 1.3 AU on (osculating) circular and coplanar objects with mean anomalies differing by 1.5 radians, and let them migrate inwards in the standard Hayashi minimum mass solar nebula (MMSN) disc model (Hayashi 1981) with surface density $\simeq 1700 \text{ g/cm}^2 (r/\text{AU})^{-1.5}$. The migration was driven by a prescription for type I gas migration Tanaka et al. (2002), in which the motion is produced by the asymmetry between the torques generated by the interior and exterior wakes of the body (Goldreich & Tremaine 1980; Ward 1986). (The difference in mass between the two test objects is to ensure that the lower-mass planet is being carried along by the resonance and not merely migrating in tandem.) Figure 10 shows the evolution of the semimajor axis and the resonant




Figure 9. Evolution of resonance angles for pairs of objects in 2:1 mean motion resonance under both DH (green) and Naoko (blue) integrators. The three cases correspond to $a_1, a_2 = (0.63 \text{ AU}, 1.00 \text{ AU})$, $(0.76 \text{ AU}, 1.20 \text{ AU})$, and $(1.00 \text{ AU}, 1.59 \text{ AU})$.




Figure 10. Semimajor axis and resonance angle for coorbital migration pair crossing transition zone (the shaded area) for DH (green) and Naoko (blue) integrators.

angle for both the DH and Naoko integrators. Even when the pair crosses the transition zone, the trajectories are barely distinguishable. It may seem counterintuitive that the algorithm performs near-perfectly on coorbital resonances which depend sensitively on the local potential and considerably worse on distant resonances which might be expected to be more forgiving of sampling errors. However, the method's errors compared with the the standard DH algorithm all involve *relative differences*, and in the case of co-orbital objects on near-circular objects, these are minimal.




Figure 11. Semimajor axis and resonance angle for pair of objects in 3:2 resonance crossing transition zone (the shaded area) for DH (green) and Naoko (blue) integrators.

3.2.3 Transition crossing

A more rigorous test comes from seeing whether resonance can be maintained when the objects are under different – and varying – terms in the Hamiltonian. We place a $10 M_{\oplus}$ planet at 1.40 AU and a $20 M_{\oplus}$ planet at 1.85 AU, just outside the 3:2 resonance at $\sim 1.83 \text{ AU}$, and turn on type I migration in the MMSN for them both. The results are shown in fig. 11. The $20 M_{\oplus}$ planet migrates faster than the $10 M_{\oplus}$ planet and catches up to the resonance within the first ~ 1000 yrs. The evolution under DH of 0.025 yr and Naoko with 0.025/0.050 yr is almost identical until the inner object enters the transition zone; that Naoko is using a timestep twice as large makes little difference. Even after the objects enter the transition region, the planets remain in the 3:2, and the libration width is comparable between the two runs.

3.2.4 Transition crossing: varying timestep ratios

It is of interest to see how the maintenance of the resonance varies as the inner:outer timestep ratio is varied. We place terms in the Hamiltonian. We place a $1 M_{\oplus}$ planet at 0.77 AU and a $10 M_{\oplus}$ planet at 1.23 AU, just outside the 2:1 resonance, and again turn on MMSN type I migration. We fix the outer timestep at 0.05 yr, and change the number of inner steps per outer step, while keeping the transition zone from 0.90 AU to 1.10 AU in each run. Figure 12 shows the resulting evolution of the resonance angle. The use of multiple timescales for the forces introduces spurious libration spikes (with corresponding behaviour in the eccentricities), with the libration width during the spikes generally increasing with the timestep ratio. However, in all cases, from 2:1 through 96:1, the integration error failed to break the resonance during the transition, and the pair returned to the correct trajectory after the outer object passed through the transition region.




Figure 12. Evolution of resonance angle for 2:1 pair crossing a transition region as the inner:outer ratio is varied; the thin line is the reference single-timestep behaviour

3.2.5 Transition crossing: effect of force frequency

As mentioned in §2.5, although we have chosen to evaluate the forces on the outermost timestep, one can vary this frequency. We repeat the test of the previous section but with the forces always evaluated on the inner timestep (and accordingly with no need for any transition function applied to the kick operators), in which the only active transitions involve the timestep on which the object is being drifted. The resulting evolution of the resonance angle is shown in figure 13. We see that using the fixed high-frequency forces results in a considerable qualitative improvement, although the multiple timescales used for the Kepler drift still generate libration spikes. This serves to bound the likely improvement we can imagine by increasing the force frequency, which is very costly. Recall that the formation scenarios we seek to study using the new method involve large particle numbers where the execution time is dominated by the force calculation – a quite different regime from the solar system modelling of Saha & Tremaine (1994).

3.2.6 Convergence

It is important to recognize that by changing the time sampling as we have done, we are unavoidably changing the dynamics of the system. Since the outer timestep remains fixed as we increase the inner timestep, and with it some fraction of the force evaluation, we are modifying the effective interaction between the inner and outer objects. For example, we consider a pair of $1 M_{\oplus}$ objects near a nominal 2:1 resonance at ~ 0.79 AU and 1.25 AU and vary the timestep and inner:outer ratio. The original outer timestep was 0.05 yr. Figure 14 shows the resulting change in eccentricity evolution for the inner object as both the inner:outer timestep ratio and the outer timestep are varied (the outer object shows similar behaviour.) As the ratio is increased in the top section of the figure – i.e. as the inner timestep




Figure 13. Evolution of resonance angle for 2:1 pair crossing for different transition region as the inner:outer ratio is varied; the heavier line corresponds to the high frequency force evaluation, and the lighter line to the standard low frequency evaluation of figure 12.

is decreased – the eccentricity evolution does converge, but it does not converge to the correct trajectory, although the relative differences in this case are not large. For a fixed timestep ratio, of course, as the outer timestep is decreased, the evolution converges as it should.

3.2.7 Close encounters

As mentioned previously, when two objects are in the same zone the close encounters are treated as in the Chambers algorithm, and we disallow encounters between objects which are not in neighbouring zones. Since it is known that accurate resolution of close encounters is quite sensitive to the effective Hamiltonian under which it is being integrated (DLL98, §4), it is reasonable to expect poor behaviour for objects undergoing close encounters in a transition region where it is undergoing drifts of different duration. A decrease in accuracy may be tolerable at these few locations in a simulation, but the objects cannot suffer dramatic instabilities.

We use the 0.9-1.1 AU, $dt=0.05$ yr/0.025 yr transition. To generate frequently-encountering systems, we placed a $5 M_{\oplus}$ planet at 1.00 AU, in the middle of the transition region, on a circular orbit and a protoplanet of $0.1 M_{\oplus}$ at 1.5 AU with $e = 0.333$ on a coplanar orbit, set all angles to 0 and varied only the mean anomaly from 0 to 2π . After removing runs in which the smaller body did not undergo an encounter, would have suffered a potential merger, or (in one case) became sufficiently eccentric that it escaped the integration region, 16 runs remained. The relative change in the energy and the Tisserand parameter $T = 1/2a + \sqrt{a(1-e^2)}$ (Murray & Dermott 1999 §3.4) is plotted in figure 15. The RMS of the maximum changes in E is ~ 0.0004 , and that of $T \sim 0.01$; the horizontal segments correspond to periods without encounters, where the conservation properties re-




Figure 14. Eccentricity evolution for inner object in near-resonant pair described in §3.2.6 for various timesteps and inner:outer timestep ratios; the system does not converge to the true path as the ratio is increased but does as the timestep is decreased.

vert to the standard non-encountering behaviour. For comparison, the equivalent RMS maximum changes for our reference SyMBA implementation with timestep 0.025 yr – with mergers disallowed, to make the integration even more difficult – were $\sim 3 \cdot 10^{-6}$ and ~ 0.003 for E and T, respectively. It is clear that the repeated close encounters in the transition zone cause a considerable decrease in accuracy, especially in the energy, but the error growth should be tolerable.

The Bulirsch-Stoer numerical integrator we use often fails, and reports its failure, at high precision for very close encounters. This is typically not a problem in practice, as the separations at which the integrator fails are usually much smaller than the distances at which we would merge the two bodies, but is an issue for small-radius dynamical problems. The same failure mode exists when no transition zones are involved and the symplectic algorithm is one resembling that of Chambers.

3.3 Full example: short-period Neptunes

As a case study, we consider the problem of forming short-period Neptunes, which are particularly mysterious. It is clear they did not form at the small orbital radii at which they are currently found, and so it is likely they have migrated in from further out. However, their masses – $10M_{\oplus}$ and higher – are unexpected. They are large enough that the timescale for type I migration to drag them into the Sun is considerably shorter than the formation timescale, but too small for some plausible mechanisms for suppressing type I migration to be effective (such as the opening of a gap in the disc at the transition to type II migration.)

There are two main scenarios present in the literature




Figure 15. Energy conservation and variation of Tisserand parameter during close encounters described in §3.2.7.

for forming these objects. The first, due to Alibert et al. (2006), concentrates on sophisticated gas physics and follows the evolution of effectively isolated cores through the disc as they grow via planetesimal accretion and migrate, and finally have their atmospheric mass reduced after arriving in the short-period region by evaporation. The second, due to Terquem & Papaloizou (2007), takes a more traditional N-body approach, and follows the evolution of a small number of large embryos in the inner region. Neither of these are easy to reconcile with the standard oligarchic growth model for core formation (Kokubo & Ida 1998): the first requires core formation to be suppressed everywhere in the disc except at a few special locations, and the second uses initial conditions for the mass distribution which it is difficult to recover self-consistently from earlier stages of oligarchic evolution.

It is of considerable interest whether the standard model can generate anything resembling the observed planets – if it cannot, then we have strong evidence that we are missing important physics – and the new method can address this question. We will merely sketch the application here; forthcoming work will describe our results in more detail. We apply the two-stage approach of McNeil et al. (2005), which was based on that of Thommes et al. (2003), using semianalytic approximations of oligarchic evolution to treat the early evolution of the disc and then generating an N-body realization when the number of N-body particles needed drops to practical levels. We consider various disc models (all resembling the minimum mass model of Hayashi 1981) and different migration efficiencies.

An example of a low-resolution run is shown in figure 16 which employed 21 embryos and 212 planetesimals. The semianalytic model was run to 1 Myr for a disc with surface density proportional to $r^{-0.5}$ of ~ 3 times the standard Hayashi mass without a snow line, with nominal type I migration and aerodynamic drag (for a 1 km planetesimal size), where the e-folding time for the decay of the gas disc was 0.5 Myr. A section of the system ranging from 1.0 AU to 5.1 AU was then evolved under the new N-body code until

the gas was mostly absent. As a consequence of the semianalytic model predicting that the innermost part of the disc had gone to oligarchic completion, the embryos inside of 2.0 AU migrate inwards smoothly in tandem: there is nothing to perturb them. This results in $10.3 M_{\oplus}$ of embryo material inside of 1 AU when the gas vanishes in an apparently stable configuration. Further out, the system is still undergoing chaotic evolution. In a more realistic situation, in which there were still planetesimals around in the inner regions to perturb the embryos, they might merge, producing larger planets; or, if they merge too early, they could migrate into the Sun.

Figure 17 presents examples of the kinds of interior configurations our toy simulations produce; all are plotted at $t=3.25$ Myr. Typical results include failures in which no or almost no mass is left in the interior region (S2, S5, S7, S9); cases where the total mass is interesting from the perspective of hot Neptune formation but the embryo mass is spread out over a large number of embryos instead of being concentrated in one or two objects (S4, S8); and cases where the total mass is appealing and there are only two embryos of multiple Earth masses (S1, S3, S6) but where too much of the mass is locked up in planetesimals, possibly as a consequence of the low resolution. (Planetesimals do not self-interact in these simulations.) Even these crude simulations are useful to estimate whether the conditions are appropriate for larger integrations. We will present results from higher resolution simulations in a forthcoming publication.

4 DISCUSSION

The observed behaviour of the method (including on tests not presented above) is compatible with the principles that (1) parts of the Hamiltonian can be moved between operators with different timesteps if the transition is sufficiently smooth, (2) reversibility is more important than accuracy for secular energy conservation, and (3) decreased time resolution is not catastrophic for dynamics on much longer timescales. We emphasize that we do not claim, and have not shown, that the integrators are in any sense optimal. (Some evidence suggests that a drift-kick-drift splitting can be preferable to the kick-drift-kick splitting used here, for example; see Wisdom et al. 1996.) To use a loose analogy from the history of close encounter treatment, this approach probably lies somewhere between the hybrid methods of Levison & Duncan (1994) and the mature methods of DLL98. As always, one must bear the approximations being used in mind – small effects can accumulate to cause dramatic changes on secular timescales in ways not always easy to predict. The approximations used here have the virtue of being different from those used previously. Given the decrease in force accuracy involved, it may be best to think of the use of these methods as one would a reversible, Kepler-adapted treecode: useful for studying certain formation problems, and generally informative in a statistical sense, but inappropriate for cases where detailed dynamics are important. Potential users are advised to think carefully about whether the approximations are suited for their problems, as there are far more ways for an integration to fail in




Figure 16. Embryo evolution with time for a simulation of a disc 3 times the minimum mass with $\Sigma \propto r^{-0.5}$, with disc dissipation e-folding time of 0.5 Myr. For each embryo lines corresponding to semimajor axis, perihelion distance, and aphelion distance are drawn.

the multi-zone case than there are in standard SyMBA-style integrators.

There are several potential applications and directions for generalization we have not considered here. As discussed in section 2.3, Levison & Duncan (2000) modified the Chambers approach to handle objects which occasionally require very small timesteps, at the price of integrating the entire system numerically when such an approach occurs. The new method succeeds in decoupling such objects, and so may be practical in some cases for which their method is inapplicable (such as when ejections of low-mass objects are common). It may also be useful in studying planet formation in close binaries, for which some symplectic methods for dealing with these systems already exist (Chambers et al. 2002).

Saha & Tremaine (1994) develop ‘symplectic interpolation’ methods to improve the accuracy of their integrator, by using a symplectic prediction of the effects of H_{Kep} to better synchronize the force calculations. This would probably work here as well, in a formal sense, but it is unlikely to provide dramatic improvements, and the errors in energy and angular momentum conservation introduced by the method should be tolerable for most formation problems as they stand.




Figure 17. Mass versus semimajor axis snapshots at $T=3.25$ Myr for various runs; the larger blue circles represent embryos, and the smaller red circles represent planetesimals. The total mass in embryos (M_T) and planetesimals (m_T) in the region inside 1 AU is given in the upper left.

5 CONCLUSIONS

We have presented a new integration method which preserves most of the speed and conservation properties of standard close-encountering symplectic integrators for planetary dynamics, but introduces radial zones between which the drift and force evaluation timesteps can vary. This allows for a new tradeoff between the accuracy of the integration and the speed, one which is inappropriate for precise dynamical studies but may be of use for investigating other scenarios. We expect it to be useful for approximate N-body modelling of planetary formation problems where (1) there is a wide range of orbital velocities, (2) the majority of the material needing particle representation is in the regions with longer orbital periods, and (3) the system remains sufficiently cold that the transition regions between radial zones can be kept reasonably small. Migration scenarios of the formation of hot exoplanets satisfy all these constraints, and we are currently exploring such applications.

ACKNOWLEDGMENTS

DSM thanks Martin Duncan and Paul Wiegert for useful discussions, and thank the anonymous referee for a careful review. The authors gratefully acknowledge the support of

SFTC grant PP/D002265/1. The simulations presented in this paper were performed using the QMUL HPC facilities.

REFERENCES

- Alibert, Y., et al. 2006, *Ast. & Astrophys.*, 455, L25
- Butler, R. P., Vogt, S. S., Marcy, G. W., Fischer, D. A., Wright, J. T., Henry, G. W., Laughlin, G., & Lissauer, J. J. 2004, *Ap. J.*, 617, 580
- Chambers, J. E. 1999, *Mon. Not. R. Astr. Soc.*, 304, 793
- Chambers, J. E., Quintana, E. V., Duncan, M. J., & Lissauer, J. J. 2002, *AJ*, 123, 2884
- Duncan, M. J., Levison, H. F., & Budd, S. M. 1995, *AJ*, 110, 3073
- Duncan, M. J., Levison, H. F., & Lee, M. H. 1998, *AJ*, 116, 2067
- Goldreich, P., & Tremaine, S. 1980, *Ap. J.*, 241, 425
- Hayashi, C. 1981, *Progress of Theoretical Physics Supplement*, 70, 35
- Levison, H. F., & Duncan, M. J. 1994, *Icarus*, 108, 18
- Levison, H. F., & Duncan, M. J. 2000, *AJ*, 120, 2117
- Kinoshita, H., Yoshida, H., & Nakai, H. 1991, *Celestial Mechanics and Dynamical Astronomy*, 50, 59
- Kokubo, E., & Ida, S. 1998, *Icarus*, 131, 171
- McNeil, D., Duncan, M., & Levison, H. F. 2005, *AJ*, 130, 288
- McNeil, D., 2006, Ph.D. thesis
- Murray, C. D., & Dermott, S. F. 1999, *Solar System Dynamics* (Cambridge University Press: Cambridge)
- Rauch, K. P., & Holman, M. 1999, *AJ*, 117, 1087
- Saha, P., & Tremaine, S. 1992, *AJ*, 104, 1633
- Saha, P., & Tremaine, S. 1994, *AJ*, 108, 1962
- Skeel, R.D. 1999, *Appl. Numer. Math.*, 29, 3
- Skeel, R. D., & Biesiadecki, J. J. 1994, *Ann. Numer. Math.*, 1, 191
- Tanaka, H., Takeuchi, T., & Ward, W. R. 2002, *Ap. J.*, 565, 1257
- Terquem, C., & Papaloizou, J. C. B. 2007, *Ap. J.*, 654, 1110
- Tsiganis, K., Gomes, R., Morbidelli, A., & Levison, H. F. 2005, *Nature*, 435, 459
- Thommes, E. W., Duncan, M. J., & Levison, H. F. 2003, *Icarus*, 161, 431
- Torres, G. 2007, *Ap. J. Lett.*, 671, L65
- Touma, J., & Wisdom, J. 1993, *Science*, 259, 1294
- Touma, J., & Wisdom, J. 1994, *AJ*, 107, 1189
- Ward, W. R. 1986, *Icarus*, 67, 164
- Wisdom, J. 2006, *AJ*, 131, 2294
- Wisdom, J., & Holman, M. 1991, *AJ*, 102, 1528
- Wisdom, J., Holman, M., & Touma, J. 1996, *Fields Institute Communications*, Vol. 10, p. 217, 10, 217
- Yoshida H., 1993, *Celest. Mech.*, 304, 27